Change Order Request for CWAs

			DA	TE:	2/15/2016						
1.	CONTRACTOR CHANGE REQUEST NO.	1	2.	РМ	ORDER NO./PCC	31164908					
3.	CONTRACTOR	Veteran Power	4.	CON	ITRACT NO.	2501284353					
5.	DATE WORK OCCURED	2/15/16	6.	6. PG&E CHANGE ORDER :		1					
7.	FIELD AUTHORIZATION FORM (Y/N)	N	8.	AUTHORIZING PG&E SUPV		W. Abbott					
<u>d</u>	specific description of work that was a one), what was done and why. Also no hange order request. (i.e. exclusions in t	ote the applicable									
Request change order to cover costs for additional work not addressed in the original Cost Proposal.											
1. Due to the existing utilities found while potholing at the original locations of the #5 & #7											
enclosures. additional prospecting was required to find new locations for the enclosures.											
2. The project was redesigned twice trying to find locations for the enclosures requiring											
multiple visits for prospecting. This work was tracked on time and material as shown on the LME											
3. The final design and new locations of the enclosures require additional trench footage and											
conduit to complete the installation.											
4. Additional manhours, traffic control, materials and site restoration are required to complete											
the installation. This additional cost is shown on the unit cost breakdown.											
Total Amount of Change Order=\$60,387.27											
See Attachment 1 & 2 for LME & Unit Cost Breakdown											

10. TOTAL CURRENT CWA VALUE	
\$84,535.69	
11. TOTAL CHANGE ORDER AMOUNT	
\$60,387.27	
12. NEW CWA VALUE INCLUDING CHANGE ORDER	
\$144,922.96	

13. In addition to this document, attach an invoice listing labor and equipment classifications, hours of work, and hourly rates as applicable. Also include any sub-contractor invoices, and note their applicable mark-ups. Attach a Field Authorization Form, and LM&E's if they were utilized.

Case: 19-30088 Doc# 12217-4 Filed: 04/20/22 Entered: 04/25/22 11:56:01 Page 1

Page 1 of 1

of 3

PM311649 BOLINAS F															
		PROPOSAL & CWA QUANTITIES					T			REVISED QUANTITIES					Difference
UNIT #	CATEGORY	DESCRIPTION	U/M	Unit	Price	Total		UNIT #	CATEGORY	DESCRIPTION	U/M	Unit	Price	Total	
CT-11	TRENCH_OPEN_CUT_UG	18" WIDE (DEPTH LESS THAN 48")	PER FT	100	\$118.80	11,880.00		CT-11	TRENCH_OPEN_CUT_UG	18" WIDE (DEPTH LESS THAN 48")	PER FT	193	\$118.80	22,928.40	\$11,048.40
CT-15	TRENCH_OPEN_CUT_UG	18" WIDE (DEPTH 48.1" TO 72")	PER FT	25	\$147.40	3,685.00		CT-15	TRENCH_OPEN_CUT_UG	18" WIDE (DEPTH 48.1" TO 72")	PER FT	55	\$147.40	8,107.00	\$4,422.00
CICC-3	INSTALLATION_CONDUIT_UG	4" DB120 CONDUIT	PER FT	66	\$4.95	326.70		CICC-3	INSTALLATION_CONDUIT_UG	4" DB120 CONDUIT	PER FT	200	\$4.95	990.00	\$663.30
CICC-4	INSTALLATION_CONDUIT_UG	6" DB120 CONDUIT	PER FT	57	\$9.68	551.76		CICC-4	INSTALLATION_CONDUIT_UG	6" DB120 CONDUIT	PER FT	22	\$9.68	212.96	-\$338.80
CICC-2	INSTALLATION_CONDUIT_UG	3" DB120 CONDUIT #7 EQUIPMENT/SPLICE BOX ENCLOSURE(4'6" X 8'6"X	PER FT	0	\$3.73	0.00		CICC-2	INSTALLATION_CONDUIT_UG	3" DB120 CONDUIT ENCLOSURE(4'6" X 8'6"X 7'6")HEAVY FULL-	PER FT	26	\$3.73	96.98	\$96.98
CPE-27	PRIMARY_ENCLOSURES_UG	7'6")HEAVY FULL-TRAFFIC #5 EQUIPMENT/SPLICE ENCLOSURE(3'0"X 5'0"X 4'6")	EACH	1	\$11,087.00	11,087.00		CPE-27	PRIMARY_ENCLOSURES_UG	TRAFFIC #5 EQUIPMENT/SPLICE ENCLOSURE(3'0"X	EACH	1	\$11,087.00	11,087.00	\$0.00
CPE-1	PRIMARY_ENCLOSURES_UG	(INCIDENTAL NEW INSTAL)	EACH	1	\$6,094.00	6,094.00		CPE-1	PRIMARY_ENCLOSURES_UG	5'0"X 4'6") (INCIDENTAL NEW INSTAL)	EACH	1	\$6,094.00	6,094.00	\$0.00
CB-5	BELLHOLES_UG	5' OR LESS IN DEPTH (SIDEWALK)	PER SQ/FT	80	\$82.84	6,627.20		CB-5	BELLHOLES_UG	5' OR LESS IN DEPTH (SIDEWALK)	PER SQ/FT	80	\$82.84	6,627.20	\$0.00
CO-1	OTHER_UG	TRAFFIC CONTROL	COST PLUS	7	\$2,000.00	14,000.00		CO-1	OTHER_UG	TRAFFIC CONTROL	COST PLU	S 12	\$2,000.00	24,000.00	\$10,000.00
CR-16	RESTORATION_CLASS2BASE_UG	GREATER THAN 500 SQ/FT (6.1-12")	PER SQ/FT	940	\$4.13	3,882.20		CR-16	RESTORATION_CLASS2BASE_UG	GREATER THAN 500 SQ/FT (6.1-12")	PER SQ/FT	1240	\$4.13	5,121.20	\$1,239.00
CR-6	RESTORATION_AC_PAVING_UG	251-500 SQ/FT (6.1-12")	PER SQ/FT	240	\$18.85	4,524.00		CR-6	RESTORATION_AC_PAVING_UG	251-500 SQ/FT (6.1-12")	PER SQ/FT	740	\$18.85	13,949.00	\$9,425.00
CR-31	RESTORATION_SIDEWALK_UG	251-500 SQ/FT (4.1-8")	PER SQ/FT	700	\$16.90	11,830.00		CR-31	RESTORATION_SIDEWALK_UG	251-500 SQ/FT (4.1-8")	PER SQ/FT	700	\$16.90	11,830.00	\$0.00
CR-37	RESTORATION_CURB_GUTTER_UG	0-50 LF	PER LF	0	\$837.30	0.00		CR-37	RESTORATION_CURB_GUTTER_UC		PER LF	30	\$55.90	1,677.00	\$1,677.00
CCR-8	CIVIL_CREW_RATE_UG	CLEARANCE 4 MAN CREW WITH CREW TRUCK (PREMIUM TIME)	PER HR	12	\$837.30	10,047.60		CCR-8	CIVIL_CREW_RATE_UG	4 MAN CREW WITH CREW TRUCK (PREMIUM TIME) ADDITIONAL TIME FOR PROSPECTING TO	PER HR	12	\$837.30	10,047.60	\$0.00
									LME	FIND LOCATION OF ENCLOSURES. THIS WORK TRACKED ON LME	LUMP SUN	M 1		22,154.39	\$22,154.39
					Total	\$ 84,535.46							Total \$	144,922.73	\$60,387.27

SELECT DROP DOWN IN THESE FIELDS Daily Statement of Labor, Material, and Equipment - Furnished by Contractor 1/26-1/28 ADD'L
PROSPECTING AT NEW
LOCATIONS FOR PLACEMENT
OF ENCLOSURES. STILL NO
WINDOW FOUND. FIELD MEET
WITH ANDTY WELCH'R DAVID
BROWN TO REDESIGN PROSPECTING ABOVE THE
AMOUNT NUCLUBED IN
CONTRACT. PROSPECT AT LOC
2 & 7 FOR PLACEMENT OF #S
8 #7 ENCLOSURES. MOVE TO
ALLEY WAY AND PERFORM
ADDIL POTHOLING. NO
WINDOW WAS FOUND. JOB LOCATION: Number of person/days 31 BOLINAS FAIRFAX 11/30-1/28 Date CONTRACT OR SPEC. NO. PM31164908 JOB NO. VETERAN POWER, INC. CHANGE ORDER NO. SHEET OF SHEETS CONTRACTOR'S LABOR NAME LABOR TYPE RATE HRS TOTAL \$ RENTAL EQUIPMENT Foreman IBEW 110.90 ST 2,218.00 ST 20.00 **EQUIPMENT DESCRIPTION** RATE AMOUNT ITEM 1.00 412.50 BEN OGDEN OT OT # # TRENCH PLATES/SHORING DELIVERY & PICK UP 196.53 DT Line Equip. Man IBEW 84.45 ST 1,689.00 ST 20.00 20.00 DONNY FRIEMOTH OT OT # # TOTAL EQUIPMENT RENTAL 412.50 145.95 DT Groundman IBEW 68.71 ST 20.00 1,374.20 ST 20.00 ADDITIONAL SERVICES MANNY SAMANIEGO OT OT DT SERVICE DESCRIPTION RATE AMOUNT ITEM 114 03 DT Foreman IBEW TRAFFIC CONTROL-DAYS 3.00 2,166.75 6,500.25 68.71 ST 18.00 1,236.78 ST 18.00 JESUS MORENO ОТ OT 114.03 DT DT Line Equip. Man IBEW 84.45 ST 18.00 1.520.10 ST 18.00 CRUZ LOPEZ - OT OT 145.95 DT DT Groundman IBEW 1,236.78 ST 18.00 68.71 ST 18.00 6,500.25 FRANCISCO TORRES ОТ OT TOTAL ADDITIONAL SERVICES # 114.03 DT DT MATERIAL \$ TOTAL ITEM Groundman IBEW 68.71 ST 1,236.78 ST 18.00 JOSE BARBOSA OT OT # 114.03 DT LABOR TYPE ↓ ST ST ОТ OT LABOR TYPE ↓ ST ST TOTAL MATERIAL OT CONTRACTOR OWNED EQUIPMENT OT EQUIPMENT DESCRIPTION DT HRS RATE AMOUNT LABOR TYPE ↓ ST ST CREW TRUCK 38.00 32.00 1,216.00 OT OT # # # 5 YRD DUMP TRUCK 38.00 35.00 1,330.00 DT DT **EQUIPMENT TRAILER** 38.00 8.00 304.00 1,140.00 F35 MINI FXCAVATOR 38.00 30.00 800 GALLON VACUUM EXCAVATOR 20.00 37.00 740.00 TOTAL OWNED EQUIPMENT 4,730.00 TOTAL PREMIUM TIME (DT) TOTAL PREMIUM TIME (OT) TOTAL STRAIGHT TIME (ST) 10,511.64 10,511.64 TOTAL RENTAL EQUIPMENT COST 412.50 PAYROLL TAXES ON TOTAL LABOR OF \$ 6,500.25 Inc. Above TOTAL ADDITIONAL SERVICES FT/EA COMP. INS. ON TOTAL LABOR OF \$ Inc. Above TOTAL MATERIAL & SALES TAX TOTAL CONTRACTOR OWNED EQUIP 4,730.00 P.L. AND P.D. ON TOTAL LABOR OF S Inc. Above WELFARE Inc. Above SUBSISTENCE - DAYS TOTAL 11,642.75 **GRAND TOTAL** TOTAL LABOR, P/R TAXES, ETC. 10,511.64 22,154.39

Case: 19-30088 Doc# 12217-4 Filed: 04/20/22 Entered: 04/25/22 11:56:01 Page 3